

6.

ಬೆವಿಕಂ



BANGALORE ELECTRICITY SUPPLY COMPANY LIMITED

(Wholly owned Government of Karnataka undertaking)

No.: SEE/BCS/EE(O)/AEE-2/L/O-05/12-13

Encl:

7617-19

Superintending Engineer, C, O&M,
Bangalore South Circle, BESCOM
No. 14/3, 3rd Floor, Maharshi
Aravinda Bhavan, Nrupathunga Road,
Bangalore-560 001.

Date:

10 AUG 2012

To
Sri. H.K. Ganesh,
Sy No. 15 & 18,
Nettigere Village,
Uttarahalli,
Bangalore,
Sir,

Sub: Electrification of proposed Residential Layout to an extent of **498KW+5HP** in favour of Sri. H.K. Ganesh, Sy No. 15 & 18, Nettigere Village, Uttarahalli, Bangalore.

Ref:- Ltr. No. HSR/EE/AAE(O)/JE-1/3138 dt: 31.07.2012.

With reference to the above approval is hereby accorded to execute the work of Electrification of proposed **Residential layout of 124 sites in favour of Sri. H.K. Ganesh, Sy No. 15 & 18, Nettigere Village, Uttarahalli, Bangalore**, subject to the following conditions:-

1. You have to pay the following amounts at O & M S-12 Sub-Division, BESCOM, Bangalore within a period of **One month from the date of this letter failing which the sanction will be stand cancelled.**

♦ **10% SC Charges - Rs. 3,03,160/- (Rupees Three Lakhs Three Thousand One Hundred and Sixty Only). Cost of self Execution Estimate Rs. 30,31,571/-.**

2. You have to carry out the work involved for electrification of proposed residential layout at your own cost under self-execution, through a Class-I Electrical contractor as per the estimate approved by the Executive Engineer (Ele.) [C,O&M] **HSR Division**, BESCOM, Bangalore as detailed here under you should carryout the line extension work, such as:-

Proposals:-

1. Extension of 11KV line to a distance of about 1.8km from F1 feeder of Somanahally MUSS.
2. To provide 2Nos. of DP Structure.
3. Extension of 11KV line inside the layout to a distance of 480mtrs using 11KV ABC cable of size 3x95 + 1x70Sq.mm.
4. To install 3x250KVA Transformer inside the layout.

..2)

5. Extension of LT line using LT ABC 3x95 + 1x70 + 1x60 Sq.mm to a distance of 1.1km.
6. To provide 3Nos. of LT feeder pillar boxes.
7. To provide 30nos of street light fittings.
3. The materials used shall confirm to BESCO specifications wherever necessary.
4. The entire distribution system with the connected equipments will be taken over by BESCO after completion of the works.
5. Guarantee shall be furnished for a period of not less than one year for the materials used in the works as well as for the quality of the work carried out from the date of taking over of the lines and equipment's by BESCO.
6. Proof of having purchased the materials used for executing the works from the BESCO Vendor approved firm will be verified wherever necessary.
7. After payment of supervision charges, work order will be issued by the **Executive Engineer, (El.) C,O&M, HSR Division, BESCO, Bangalore.**
8. The developer shall execute an agreement on Rs. 200/- stamp paper of required denomination, affirming his consent to maintain the lines and transformer centers erected in the layout till 25% of the Applicants avail power supply to the houses in the layout. After the completion of works satisfactorily by the developer and after a minimum of 25% of the applicants avail power supply in the layout, the entire Distribution System along with the transformer (S) shall be taken over by the Distribution Licensee, without payment of any charges for the purpose of maintenance.
9. Materials procured by prospective consumers in respect of self execution works shall confirm to BESCO specification and shall be inspected by the jurisdictional Executive Engineer Ele., C, O&M or his authorized representatives. The Executive Engineer Ele./Asst. Executive Engineer Ele., C, O&M sub division shall ensure that materials are purchased from approved vendors or materials can be sourced from any agency/company who is technically qualified in BESCO/ESCO/LPTCL tenders within 2 years from the starting of the financial year. Proof of having purchased the materials used for executing the works will be verified wherever necessary.
10. And other conditions specified in the Addl. clause 3-2-1 of conditions of Supply of Electricity should be fulfilled.
11. The material inspection fee shall be paid at sub division office as per the circular CYS-26 dtd 27.06.2011 of General Manager, TA&QC.
12. The existing 11KV line with Transformer shall be released & return to store before energisation of layout.

Yours faithfully,


(D. Nagarjuna)

**Superintending Engineer Ele., (C,O&M),
Bangalore South Circle
BESCO Bangalore.**